

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
		Sub Head - Sanitary Installations				
1	17.3	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
1.1	17.3.1	W.C. pan with ISI marked white solid plastic seat and lid	Each	35		
2	17.7A (modified)	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- (a) White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer (Jaquar Model Number (Make Jaquar Modal 5357N)	Each	35		
3	17.10 (modified)	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 fixed with C.I. brackets or on platform counter and stainless steel plug 40 mm, waste coupling including painting of fittings and brackets, cutting and making good the walls wherever required etc. complete in all respect.				

Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
3.1	Non DSR Item 17.10.1.A (Modified)	Kitchen sink with drain board Model No SBSD-01 (RR) Make Jayna Jupiter Series	Each	3		
3.2	Non DSR Item 17.10.1.B (Modified)	Kitchen sink with drain board Model No OR-01, Make Jayna Oracle Series	Each	12		
3.3	Non DSR Item 17.10.1.C (Modified)	Kitchen sink with drain board Model No DBSD-01 (DX), Make Jayna Mercury Series	Each	2		
4	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	17.28.2	Flexible Pipe				
4.1	17.28.2.1	32 mm dia	Each	54		
5	17.29	Providing and fixing 100 mm sand cast Iron grating for gully trap.	Each	12.00		
6	17.31 (modified)	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with S.S. Stud complete in all respect.	Each	18.00		
6.1	Non DSR Item	Providing and fixing 900x450 mm beveled edge mirror of superior glass (of approved quality) complete with S.S. Studs complete in all respect.	Each	17.00		



Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
7	17.33	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete.	Each	35.00		
8	17.34	Providing and fixing toilet paper holder :				
8.1	17.34.1	C.P. brass	Each	6.00		
9	Non DSR Item	Providing and fixing uPVC Soil pipes Type "B" make Supreme, including sockets, complete, as waste and soil pipes, all as per directions of Engineer-in-Charge:				
9.1	Non DSR Item	160 mm dia uPVC Type B make Supreme	meter	100		
9.2	Non DSR Item	110 mm dia uPVC Type B make Supreme	meter	190		
9.3	Non DSR Item	75 mm dia uPVC Type B make Supreme	meter	150		
10	Non DSR Item	Providing and fixing Metal Clamp for uPVC pipes on walls, of approved design anchored with fasteners, and making good the walls etc. complete as directed, as of size:				



Signature SET's Representative
with date **28 May 2023**

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage


Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
10.1	Non DSR Item	for 160 mm dia uPVC Type B make Supreme	Each	40		
10.2	Non DSR Item	for 110 mm dia uPVC Type B make Supreme	Each	80		
11	Non DSR Item	Providing and fixing Cowl / Terminal Guard of uPVC make Supreme				
11.1	Non DSR Item	for 150 / 160 mm dia uPVC Type B make Supreme	Each	8		
11.2	Non DSR Item	for 100 / 110 mm dia uPVC Type B make Supreme	Each	12		
12	Non DSR Item	Providing and fixing double unequal junction of required degree with access door, complete:				
12.1	Non DSR Item	150x150x100x100 mm or 160x160x110x110 mm	Each	32		
12.2	Non DSR Item	110x110x75x75 mm or 100x100x75x75 mm	Each	48		
13	Non DSR Item	Providing and fixing shoe bend uPVC make Supreme				

Signature SET's Representative
with date 28 May 2023




Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
13.1	Non DSR Item	160/150mm dia	Each	5		
13.2	Non DSR Item	110 / 100 mm dia	Each	5		
14	Non DSR item	Providing and fixing uPVC plain bend of required degree, heavy duty, make Supreme				
14.1	Non DSR item	160 / 150mm dia	Each	8		
14.2	Non DSR item	110 / 100 mm dia	Each	70		
14.2	Non DSR item	75 mm dia	Each	60		
15	Non DSR Item (Modified from 17.60)	Providing and fixing uPVC trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors , including SS jaali of size 100 mm :				



28 May 2023

Signature SET's Representative
with date


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
15.1	Non DSR Item (Modified from 17.60.2)	100 mm inlet and 75 mm outlet	Each	160		
16	Non DSR Item	Providing & fixing of Single Towel Rail of size 600mm long 600 mm long with necessary SS Screw with pvc sleeves. (Make Jaquar, Model - ACN-1111NM). Complete in all respects.	Each	30.00		
17	Non DSR Item	Supply & fixing of CP Hand Shower (Health Faucet) with 1.2 meter long including wall hook with necessary SS screw with pvc sleeve. (Jaquar Make Model-ALD-CHR-593N)	Each	35.00		
18	Non DSR Item	Providing & fixing of Towel Rack with Lower Hanger SS with necessary SS Screw and hooks (Jaquar Make - Model- AHS-1581H). Complete in all respects.	Each	6.00		
19	Non DSR Item	Providing & fixing of Towel Ring round with round flange (Make Jaquar, Model ACN - 1121BN). Complete in all respects.	Each	35.00		
20	Non DSR Item	Supply & fixing corner glass self with bracket make Jaquar Model No- ACN - 1173.	Each	70.00		



Signature SET's Representative
with date **28 May 2023**

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
21	Non DSR Item	Providing & fixing Soap dish holder make Jaquar-Model No ACN - 1131 N fixed on wall with necessary SS Screw with pvc sleeves etc. complete in all respect.	Each	35.00		
		Total of Sanitary Works (Rs)				
Sub Head - Water Supply						
1	18.8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc				
1.1	18.8.2	20 mm nominal dia Pipes	Meter	220.00		
1.2	18.8.3	25 mm nominal dia Pipes	Meter	20.00		

Signature SET's Representative
with date 28 May 2023


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
2	Modified (18.12)	Providing and fixing G.I. pipes on external walls with clamps, complete with G.I. fittings / MTA / FTA necessary fittings complete in all respects including trenching and refilling etc.				
2.1	Modified (18.12.3)	25 mm dia nominal bore	Meter	10.00		
2.2	Modified (18.12.4)	32 mm dia nominal bore metre	Meter	30.00		
2.3	Modified (18.12.5)	40 mm dia nominal bore metre	Meter	30.00		
2.4	Modified (18.12.6)	50 mm dia nominal bore metre	Meter	80.00		
3	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
3.1	18.13.1	25 to 40 mm nominal bore	Meter	10.00		
3.2	18.13.2	50 to 80 mm nominal bore	Meter	3.00		



Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
4	Non DSR Item	Supply & Fixing of water meter and stop cock in G.I. pipe line including cutting and threading the pipe and making long screws etc. complete (cost of stop cock to be paid separately). Water Meter shall be MCD approved, with Test Certificate, Guarantee Card and with Original GST Paid bill in the name of Secretary Salwan Education Trust, Rajendra Nagar, New Delhi. Payment against this item shall be released only after receipt of complete documents.	Each	18.00		
5	18.16	Providing and fixing CP brass stop cock of approved quality ISI Marked:				
5.1	18.16.1	15 mm nominal bore	Each	9		
5.2	18.16.2	20 mm nominal bore	Each	9		
6	18.17 (modified)	Providing and fixing brass / forged brass gate valve with C.I. wheel of approved quality (screwed end), make ZOLOTO :				
6.1	18.17.1	25 mm nominal bore	Each	4		
6.2	18.17.1 A	20 mm nominal bore	Each	4		


Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
6.3	18.17.2	32 mm nominal bore	Each	8		
6.4	18.17.3	40 mm nominal bore each	Each	8		
6.5	18.17.4	50 mm nominal bore	Each	16		
7	Non DSR Item	Providing and fixing CPVC gate valve with knob /handle of approved quality (screwed end), make ASTRAL / Supreme heavy duty :				
7.1	(i)	20 mm nominal dia bore	Each	26		
7.2	(ii)	25 mm nominal dia bore	Each	26		
8	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :				
8.1	18.18.1	20 mm nominal dia bore	Each	9		



Signature SET's Representative
with date **28 May 2023**

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage


Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
8.2	18.18.2	25 mm nominal dia bore	Each	9		
9	18.20	Providing and fixing brass ferrule with C.I. mouth cover including boring and tapping the main :				
9.1	18.20.1	15 mm nominal bore	Each	6		
9.2	18.20.2	20 mm nominal bore	Each	6		
9.3	18.20.3	25 mm nominal bore	Each	6		
10	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions, fit for geysers also :				
10.1	18.21.1	30 cm length				
10.1.1	18.21.1.1	15 mm nominal bore	Each	24		
10.1.2	18.21.1.2	20 mm nominal bore	Each	24		

Signature SET's Representative
with date **28 May 2023**




Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
10.2	18.21.2	45 cm length				
10.2.1	18.21.2.1	15 mm nominal bore	Each	24		
10.2.2	18.21.2.2	20 mm nominal bore	Each	24		
11	18.22	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :				
11.1	18.22.1	100 mm diameter	Each	12.00		
11.2	18.22.2	150 mm diameter	Each	12.00		
12	Non DSR Item	Providing and fixing C.P. brass shower ARM 15 or 20 mm inlet dia, 300 mm long, with or without bend for wall mounted showers with flange, make Cera / Hindware model Contessa Plus:	Each	24.00		
13	Non DSR Item	Providing and fixing overhead shower C.P. brass shower rose with 15 or 20 mm inlet :				



Signature SET's Representative
with date **28 May 2023**

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
13.1	Non DSR Item	100 mm diameter, round shape single flow, ABS Body, Chrome plated with Gray face plate, with rubit cleaning system make Jaquar, Model No OHS-1989 with 450mm long shower arm straight 20 mm dia and 450 mm long round shape without bend for wall mounted showers with flange make Jaquar Model No - SHA-49483	Each	3		
13.2	Non DSR Item	120 mm diameter, round shape single flow, ABS Body, Chrome plated with Gray face plate, with rubit cleaning system make Jaquar, Model No OHS-1789 with 450mm long shower arm straight 20 mm dia and 450 mm long round shape without bend for wall mounted showers with flange make Jaquar Model No - SHA-49483	Each	3		
14	18.48 (Modified)	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, rotational moulded, Four / five layers, Food Grade, with cover and suitable locking arrangement, Colour White and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank, make Sintex.				
14.2	(i)	1000 litre Capacity	Per Liter	18.00		
15	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :				
15.1	18.49.1	15 mm nominal bore	Each	80.00		

Signature SET's Representative
with date  28 May 2023


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
16	Non DSR Item	Providing and fixing C.P. brass Wall Mixer Non-Telephonic Shower with connecting legs and wall flanges of approved quality and make Jaquar, Model No FLR-5219N, complete as directed by Engineer in Charge.	Each	18.00		
17	18.50	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms of approved quality and make Hindware / Cera / Jaquar.				
17.1	18.50.1	15 mm nominal bore	Each	80.00		
18	Non DSR Item	Providing and fixing CP Brass single hole Kitchen Sink Mixer of make Jaquar, Model No FLR - 5179B (FLORENTINE SERIES) , including braided hoses 450 mm long, all as complete as diirected by Engineer-inCharge	Each	2.00		
19	Non DSR Item	Providing and fixing CP Brass single hole Kitchen Sink Mixer of make Jaquar, Model No FLR - 5357N (FLORENTINE SERIES) , including braided hoses 450 mm long, all as complete as diirected by Engineer-inCharge	Each	16.00		
20	Non DSR Item	Providing and fixing CP Brass single hole Wash Hand Basin basin mixer of make Jaquar, Model No OPP - 15011BPM (OPAL PRIME SERIES) , including braided hoses 450 mm long, all as complete as diirected by Engineer-inCharge	Each	34.00		

Signature SET's Representative 
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
21	18.52 (Modified)	Providing and fixing C.P. brass stop cock (concealed) of standard design conforming to IS:8931, make Jaquar, Model No OPP-15083KPM.				
21.1	18.52.1	15 mm nominal bore	Each	12.00		
22	18.53	Providing and fixing C.P. brass angle valve, conforming to IS:8931, make Jaquar, Model No OPP-15053PM				
22.1	18.53.1	15 mm nominal bore	Each	48.00		
23	18.52 (modified)	Providing and fixing C.P. brass stop cock (concealed) of standard design conforming to IS:8931, make Jaquar/Cera/Hindware				
23.1	18.52.1	15 mm nominal bore	Each	28.00		
24	18.53 (modified)	Providing and fixing C.P. brass angle valve, conforming to IS:8931, make Jaquar/Cera/Hindware				
24.1	18.53.1	15 mm nominal bore	Each	112.00		



Signature SET's Representative
with date 28 May 2023

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage


Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
25	Non DSR Item Modified (18.21)	Providing and fixing uplasticised PVC connection pipe with brass unions, super-high tensile strength braided stainless steel ensuring maximum pressure retaining qualities, completely burst-proof, 304 grade stainless steel braided exterior, durable and flexible , Stainless steel braiding for extra protection, Heavy Stainless Steel Connection Pipe For Geyser Connection and Wash Hand Basins				
25.1	Modified	30 cm length				
25.1.1	Modified	15 mm nominal bore	Each	36		
25.1.2	Modified	20 mm nominal bore	Each	36		
25.2	Modified	45 cm length				
25.2.1	Modified	15 mm nominal bore	Each	36		
25.2.2	Modified	20 mm nominal bore	Each	36		

Signature SET's Representative
with date **28 May 2023**




Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
		Total of Water Supply (Rs)				
		Sub Head - Drainage				
1	Non DSR Item	Providing, laying and jointing UPVC pipes, Type B, (make : Supreme) including testing of joints etc. complete in all respect.				
1.1	(i)	75 mm dia meter	Meter	200.00		
1.2	(ii)	110 mm diameter	Meter	40.00		
1.3	(iii)	160 mm diameter	Meter	50.00		
2	19.2 (modified)	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes / uPVC including bed concrete as per standard design :				
2.1	19.2.1	110 mm diameter	Meter	22.00		



Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
2.2	19.2.2	160 mm diameter	Meter	25.00		
3	19.4 (modified)	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight GFRC cover with frame of 300 x300 mm size (inside) as per standard design:				
3.1	19.4.1	100x100 mm size P type				
3.2	19.4.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	5.00		
4	19.7	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :				



Signature SET's Representative
with date **28 May 2023**


Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Name of Work : Construction of Staff Residences on Plot Nos 53 / 11 to 53 / 14, Rajendra Nagar, New Delhi - 110 060

Ser No	DSR Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
4.1	19.7.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :				
4.2	19.7.1.1	19.7.1.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	10		
5	19.21	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :				
5.1	19.21.1	For pipes 100 to 250 mm diameter	Each	12.00		
		Total of Drainage Works (Rs)				
		Total of Sanitary + Water Supply + Drainage Works (Rs)				



Signature SET's Representative
with date **28 May 2023**

Civil Works : Schedule "A"
Schedule No 12 : Sanitary, Water Supply and Drainage

Signature of Contractor
or his Authorised Representative with date